Sealce Creamery HeadQuarters Network Floor Plan

MDF1

FICs

16 SM Fiber strands going to MDF2 (LC Connector) 8 MM Fiber strands going to IDF1 (ST Connector) 8 MM Fiber strands going to IDF2 (ST Connector) 8 MM Fiber strands going to IDF3 (ST Connector) 8 MM Fiber strands going to IDF4 (ST Connector)

*No Copper Patch Panels in MDF1

MDF2

FICs

16 SM Fiber strands going to MDF1 (LC Connector) 8 MM Fiber strands going to IDF1 (ST Connector) 8 MM Fiber strands going to IDF2 (ST Connector) 8 MM Fiber strands going to IDF3 (ST Connector) 8 MM Fiber strands going to IDF4 (ST Connector)

*No Copper Patch Panels in MDF2

IDF1

FICs

8 MM Fiber strands going to MDF1 (ST Connector) 8 MM Fiber strands going to MDF2 (ST Connector)

Copper Drops (Patch Panel)

35 small cubicles, 2 Ethernet ports each Total: 70 5 offices, 4 Ethernet ports each Total: 20

90 Total Drops

IDF2

FICs

8 MM Fiber strands going to MDF1 (ST Connector) 8 MM Fiber strands going to MDF2 (ST Connector)

Copper Drops (Patch Panel)

42 small cubicles, 2 Ethernet ports each 3 offices, 4 Ethernet ports each Total: 84 Total: 12 3 small conference rooms, 8 ports each Total: 24

120 Total Drops

<u>IDF3</u>

FICs

8 MM Fiber strands going to MDF1 (ST Connector) 8 MM Fiber strands going to MDF2 (ST Connector)

Copper Drops (Patch Panel)

30 network drops in Cafeteria Total: 30 35 small cubicles, 2 Ethernet ports each Total: 70 3 offices, 4 Ethernet ports each Total: 12 4 small conference rooms, 8 ports each Total: 32

144 Total Drops

IDF4

FICs

8 MM Fiber strands going to MDF1 (ST Connector) 8 MM Fiber strands going to MDF2 (ST Connector)

Copper Drops (Patch Panel)

36 ports in large conference room Total: 36
42 small cubicles, 2 Ethernet ports each Total: 84
5 offices, 4 Ethernet ports each Total: 20


Total: 20 140 Total Drops

Internet Demarc

Copper Ethernet

Century Link

Handoff



Internet Demarc Comcast LC SM Fiber Ethernet Handoff 100 Mbos